


Bubble Chamber Experimental Readiness Review

September 11, 2014

[https://wiki.jlab.org/ciswiki/index.php/Bubble Chamber](https://wiki.jlab.org/ciswiki/index.php/Bubble_Chamber)

ASTROPHYSICAL S-FACTOR $^{12}\text{C}(\alpha,\gamma)^{16}\text{O}$



OUTLINE

- Beam Requirements
- Bubble Chamber
- Beamlines (Test and Experiment)
- Test Beamline Commissioning
- Schedule
- Safety Reviews
- Readiness Documents


BEAM REQUIREMENTS

I. Beam Properties at Radiator:

Beam Kinetic Energy, (MeV)	7.9–8.7
Beam Current (μA)	0.01–100
Absolute Beam Energy Uncertainty	<0.1%
Relative Beam Energy Uncertainty	<0.02%
Energy Resolution (Spread), σ_T/T	<0.06%
Beam Size, $\sigma_{x,y}$ (mm)	1–2
Polarization	None

Bubble Chamber
at HIGS
April 2013

Photon Beam
Entrance








N_2O Bubble Chamber

$T = -5^\circ\text{C}$


$P = 60 \text{ atm}$

First $\gamma + \text{O} \rightarrow \alpha + \text{C}$ bubble

April 2013



CEBAF 5 MeV REGION



BCM

5 MeV
Dipole

5D
Spectrometer

2D
Spectrometer

Mott
Polarimeter


Bubble
Chamber
location

NEW BEAMLINE ELEMENTS


New Beamline elements installed in support of Bubble Chamber experiment:

I. Fast Valve after $\frac{1}{4}$ Cryounit


protect from
vacuum failure in
front of $\frac{1}{4}$ Cryo-unit




II. New MDL0L02 Dipole Magnet





EXPERIMENT BEAMLINE





TEST BEAMLINE










- Use pure Copper and Aluminum
- Radiator/dump isolated and current in EPICS readback



TEST BEAMLINE COMMISSIONING

- New Test Beamline is ready for Fall 2014 run
- Commissioning plan will be submitted:
 - I. Checklist of machine protection interlocks and controls (no review is required)
 - II. Checkout of beamline with electron beam
- Beam Studies:
 - I. Momentum measurement
 - II. Measure Bremsstrahlung spectra
 - III. Operation at high current
 - IV. Measure beam charge at different currents

SCHEDULE

May 3 – September 18, 2014	Summer Shutdown, CHL@4K
September 19 – December 22, 2014	2.2GeV/pass
Fall 2104	Bubble Chamber commissioning at HIGS
December 23, 2014 – February 5, 2015	Winter Shutdown, CHL@2K
February 6, 2015 – June 12, 2015	Hall A Physics, Hall D Eng. Run
June 13, 2015 – September 10, 2015	Summer Shutdown, CHL@2K (?)


Commission Test
Beamline

1st Opportunity
in January

2nd Opportunity
in Summer


For helium
processing of
Cryo-modules

EXPERIMENT BEAMLINE REVIEW




BUBBLE CHAMBER SAFETY REVIEWS

- Superheated liquid: N_2O , Nitrous oxide (laughing gas)
 - I. At room temperature, it is colorless, non-flammable gas, with slightly sweet odor and taste



- High pressure system:
 - I. Design Authority: Dave Meekins
 - II. $T = -5^\circ\text{C}$
 - III. $P = 60\text{ atm}$

- Buffer liquid: Mercury
 - I. Closed system
 - II. Volume: 135 mL



All done at
Argonne. How to
transfer to JLab?

READINESS DOCUMENTATION

1. Conduct of Operations (**COO**)
2. Experiment Safety Assessment Document (**ESAD**)
3. Radiation Safety Assessment Document (**RSAD**)
4. Operational Safety Procedures (**OSP**)

Similar to
PEPPo