



# EIC Beam Pipe Test Stand Functionality Test

Marc McMullen, George Jacobs, Brian Eng  
Detector Support Group  
January 4, 2023


# Contents

- Objective
- EIC Beampipe Diagram
- Simulated Beam Line Assembly
- Pressure System Installation
- Assembled Beampipe
- Controls and Monitoring
- System Test (12/16/2022)
- Conclusion

# Objective


- Assemble simulated beam line test stand
  - The simulated beam line uses off-the-shelf components that are of similar dimensions to the actual beam line
  - Test stand will be used to validate [Ansys simulation of beampipe bakeout](#) and the effects on the first silicon tracking layer
- Develop controls and monitoring system
- Test the system for functionality

# EIC Beampipe Diagram



- RTD\_A, B and C are inside the 3.5" airflow pipe
- RTD\_Heater is on the outside of the 2.5" heated pipe
- The O-ring blocks one end of the 3.5" pipe to direct the flow of air


# Simulated Beam Line Assembly



Beam line components were rough assembled to get the proper alignment of the pipe stands




# Pressure System Installation



- The pressure system components consist of a relief valve, an orifice, a regulator, and a 250 slm MFC
- All pressure system components were tested by a JLab design authority prior to use


# Assembled Beampipe





After all pipes were aligned, the immersion heater pipe was installed and filled with mineral oil

# Controls and Monitoring

Monitoring display



Heater controls





MFC controls

- A LabVIEW program monitors the temperature, controls power to the heater and the MFC
- All values are written to global variables which are displayed independently of the program
- All the global variables are recorded via a data logging program, which runs in the main



# System Test (12/16/2022)



- The system was tested for 4.5 hours to ensure the system was functioning as expected
- The temperature at RTD\_Heater increased from 21°C to 78°C in ~3 hours
- 20 slm of air was flowed for an hour, which decreased the temperature at RTD\_Heater by 5°C

# Conclusion

- All components and controls elements worked as designed
- All temperatures and airflow are logged for analysis
- Simulation of the EIC beamline heating will begin in January 2023

End

Thank You