
MOLLER Internal Final Design Review

Magnet Power Supply and I&C

Brian Eng JLab On behalf of Magnet Group, DSG, DC-Power

December 6th, 2022







Outline

- Magnet Power Supplies (MPS)
 - -Overview
 - Status/Milestones
 - Prototype
- FMEA and Magnet Interlocks
- Instrumentation and Controls (I&C)
 - Overview
 - -Sensors
- Summary




MPS – Overview

- Each torus has its own separate power supply
 - -All supplies are monopolar (Nominal)

Magnet	Current (A)	Voltage (V)	Power (kW)
Upstream	1075	77.5	84
Downstream - 1	2230	40	90
Downstream - 2	2440	42	103
Downstream - 3	3372*	57	185
Downstream - 4	3350	224	751

- Nominal values, capable of peak values at 120%
- Stability of 100 ppm over 24 hr and absolute accuracy of ±50 ppm
- 95% efficient at full load
- Full specifications see: PMAG0000-0100-A0014





MPS - Status

Key Milestones

Activity	Start	End	
Power Supplies, Leads and Jumpers 60% Design Effort	08-Mar-21	30-Apr-21	COMPLETE
Power Supplies, Leads and Jumpers 90% Design Effort	10-Jan-22	07-Mar-22	COMPLETE
DS Toroid Power Supplies (DS3). On order with OCEM, Italy	Feb 2022	June 2023	DS3 Prototype MPS on order
US and DS (DS1, 2 & 4) Toroid Power Supplies, Leads and Jumpers	At CD-3a		
Instrumentation and Control (H/W and S/W) – Prototype and production	Sept 2021	Sept 2023	


Status of activities

- Power Supplies Functional requirements PMAG0000-0100-S0015 MOLLER (COMPLETE)
- Physics and Engineering Requirements for Magnet Power Supplies (COMPLETE)
- Magnet Power Supplies Specification Document both US & DS PMAG0000-0100-A0014 (COMPLETE)
- Hall A Location of PSUs and Lead Routing (COMPLETE) (Drawings to be approved)
- Water-Cooled Leads, Air-Cooled Jumpers PMAG0000-0100-S0017 (COMPLETE) and Interfaces (IN PROGRESS)
- Control, Instrumentation Drawings (IN PROGRESS), P&ID COMPLETE
- Environment Safety and Health (IDENTIFIED AND INCORPORATED AS REQUIRED, based on FMEA)
- Magnet test lab set-up for the prototype coil Low Power test (COMPLETED on SC3 and IN PROGRESS with tests for SC4)



MPS Prototype – DS3

- Schedule
 - Order placed on April 2022
 - Design review completed Aug 2022
 - Document UT-RT-0872
 - Critical components procured by vendor
 - DCCT in hand
 - FPGAs due end of Jan 2023
 - Factory acceptance testing March 2023
 - JLab staff on-site (Italy)
- Dimensions
 - -2810.4 mm (L) x 1613.5 mm (D) x 1900mm (H)
- Weight 2500 kg



Note: DS3 chosen with highest current that can be used to charge all 4 magnets (US and DS1-2-3) and DS4 with limited power to due to wall power availability in the test lab! Full power available in Hall A.




FMEA - Magnet coils, Water leaks used to develop Interlocks

Parameter	Action	Severity Level
Voltage Tap High	Trip MPS	Primary
Temperature High	Trip MPS	Primary
Water Distribution Flow Low	Trip MPS	Primary
Water Pressure Low	Trip MPS	Primary
Vacuum High	Ramp Down MPS	Secondary
Chiller Failure	Ramp Down MPS	Secondary
Window Shutter	Ramp Down MPS	Secondary

I&C: Magnet Interlocks and Protection

- Primary protection is accomplished using hardwired multi-channel voltage tap readout
- A second multi-channel voltage tap readout runs through a PLC
- Each chassis reads the same VTs and performs the comparator function in parallel
- Voltages compared during three powering states
- All hardwire interlocks shared with system master digital input for monitoring and diagnostics
- Heartbeat messages are sent across nodes via Ethernet allowing automated response during communication outages
- Secondary protection is on outlet temperature, and flow of each coil



Philosophy

- Utilize similar hardware and software that was used in previous designs as much as possible, skilled labor available as well as being familiar to end users
- Use COTS products whenever feasible (Only when technical specifications can't be met look to custom solutions)
- Redundancy on common failure points Power circuit, networking, sensors (VTs, temperatures, etc), when not feasible have spares available, e.g. PLC modules


Data Storage / Management

- PLC controller onboard SD Card to store critical events/data
- Main data handling done by EPICS soft-IOC that uses Ethernet/IP driver to communicate with PLC over network (same setup successfully used at JLAB - Hall B and D)
- Once in EPICS use Mya to archive/retrieve data (Accelerator developed and maintained, used sitewide as tool to interface with live/historical EPICS data)



I&C – Protection System Layout

- Primary Control provided by master processor with 1gbit Ethernet Interface
- Dual Ethernet Interface (i) JLAB: IOC/EPICS and (ii) Private Local Network (PLN) for critical instruments
- Direct Interlock capability 5 or 24 VDC (e.g. voltage, temperature, field, flow, etc.)
- Each Chassis (dedicated to each magnet US and DS1-4) can independently safe out the system





I&C – Sensor Types/Location/Channel Counts

- I. DS Torus Magnets: Drawings A09005-15-00-0101 / 102 / 103 / 104
 - 52 RTDs (52 redundant sensor will be installed but not cabled to PLC)
 - 10 Klixons (thermal switches)
 - 56 voltage taps (56 redundant taps will be installed and cabled to VT chassis)
 - 3 vacuum gauges
- II. US Torus
 - 7 each: Flow switches, Klixons
 - 1 DP sensor
 - 8 RTD's (redundant sensor will be installed but not cabled to PLC)
 - 2 voltage taps

III. US Collimators

- 4 Each Limit switches, Flow switches, Pneumatic valves, Temperature Switches
- 5 RTD's (+2 for Collar 0 JLab Scope)
- 1 each Flow meter, Liquid Level
- 2 Pressure transmitters

- IV. Magnet Cooler (LCW Chiller): Drawing A09005-15-00-0106
 - 8 pressure transducers
 - 9 RTDs
 - 4 control valves
 - 3 flow meters
 - 2 conductivity monitors, 2 pumps
 - 1 each: heater, UV lamp, liquid level

V. Water Distribution: Drawing A09005-15-00-0111

- 7 RTDs
- 5 each: flow meters, control valves
- 6 pressure transducers



I&C – Risk Reduction

- PLC system is main component of the I&C, both in terms of cost and scope (anticipate delivery April 2023)
- Allen-Bradley (A-B) ControlLogix previously used for both Hall B & D magnets
- Investigating other vendors due to cost increases and potential lead time issues
 - A-B prices increased ~15% from quote in 2021 to 2022
 - Siemens PLCs used by Safety Group at JLAB
 - Siemens has higher channel count and costs less than comparable A-B unit
 - Prototype (Siemens) setup to be ordered (controller + one of each module)



Summary

- ✓ MPS Order in place for the prototype MPS (DS3)
- ✓ The WCL and jumpers specification(s) are complete
- ✓ Instrumentation and control philosophy is defined
- ✓ P&IDs are in place and list of instrumentation is complete, wiring diagrams are in progress
- ✓ Magnet Protection/Interlocks fault logic has been generated
- ✓ Hardware and software development required for the system are identified and the work is in progress

Appendix

- A. MPS All 5 MPS Requirement
- B. Final P&ID's for TM4, Cooler, and Water Distribution
- C. Magnet Power Supplies: Prototype testing
- D. MOLLER Mapping REQUIREMENTS
- E. MOLLER Electrical Safety




DETAILS	US Coil	SUB-COIL #1	SUB-COIL #2	SUB-COIL #3	SUB-COIL #4
NI (Nominal) – Physics (in Ampere-Turns)	5357.5	8914.8	12192.3	19391.3	33534
Normal Operating Current (A)	1071.5	2228.7	2438.5	3372.4	3353.4
Temperature (C) and B (T) for design	70/0.5	70/0.5	70/0.5	70/0.5	70/0.5
Voltage drop across 1 coil (V)	7.58	3.78	3.93	5.27	27.45
Voltage drop with all 7 coils in series (V)	53.03	26.48	27.52	36.89	192.14
Coil interconnect (splices + bus/leads) all (V)	9.87	10.59	8.81	9.84	18.98
1. Voltage drop across coils all (V)	62.90	37.07	36.33	46.73	211.12
1a. Power loss in Magnet (kW), VI	67.40	82.62	88.59	151.03	708.00
2. Voltage drop across – Air-Cooled Jumpers (both ends) + Water cooled leads 27 m long (V)+Jumpers vacuum end (CS1-2: 3kA and CS3-4: 4kA) +0.200V (all bolted connection)	2.09	2.09	2.09	2.00	2.00
2a. Power loss between magnet and MPS (kW): Air-Cooled Jumpers (both ends) + Water cooled leads 27 m long (V)+Jumpers vacuum end (CS1-2: 3kA and CS3-4: 4kA) +equivalent to 0.200V (all bolted connection)	6.5	6.5	6.5	8.3	8.3
Total Voltage drop (V _{Total}) across the magnet seen at Magnet Power Supply terminals (V), 1+2	65	40	39	49	213
Power requirement (kW) <i>(includes all 7 coils in electrical series), 1a+2a</i>	74	89	95	160	716

Note- US coil total voltage drop and power is an estimate only



Typical P&IDs for TM4, Cooler, and Water Distribution



Magnet Power Supplies


son Lab



GUI set-up and readouts partially retired during Protoptype test in Mag Meas lab MOLLER highbay Controls Rack:

- 64bit aarch64 SBC
- SOC FPGA ADC/DAC
- FPGA raw data through RS232
- scaled/corrected data through SOC 1Gb Ethernet (mqtt)
- PT1000's, Vt's, and flow measurement
- Front development testing design
- HDL development testing
- CompactLogix PLC
- Magnet Control & Monitoring
- MPS Control

MOLLER Pr	ototype MPS Control		MOL	LER Prototy	/pe PLC Monitoring					
Turn OFF MPS	Local/Remote	1.0000			Interlock Output					
oint 228.00	Status	0.00			Klixon Thermal Switches					
	I MAX (software)	350.00	RTDT1 Coil 1 Inlet Temp	39.2 C	DVC1 Voltage	6.308 V				
terlock Summary ———	Current (MPS)	227.00	RTDT2 Coil 1 Outlet Temp	31.4 C	DVC1 Voltage	7.264 V				
Magnet Temp	Current (PLC)	227.00	RTDT3 Coil 2 Inlet Temp	38.4 C	DVC3 Voltage	8.173 V				
Magnet Water DC OverCurrent			RTDT4 Coil 2 Outlet Temp	31.2 C	DVC4 Voltage	9.156 V				
DC OverVoltage	Voltage(PLC)	31.00	RTDT5 Coil 3 Inlet Temp	39.0 C	DVC1-4 Voltage	7.476 V				
MPS Water	PS ID	0.00	RTDT6 Coil 3 Outlet Temp	31.3 C	PT1 Pressure	45.21 psi				
MPS Overheat	Polarity	0	RTDT7 Coil 4 Inlet Temp	38.371 C	PT2 Pressure	88.83 psi				
AC OverCurrent	Reset PLC In	nterlocks	RTDT8 Coil 4 Outlet Temp	31.354 C	FT1 Flow	3.88 gpm				
Fuse	Reset MPS I	nterlocks	MOLLER Prototype FPGA Monitoring							
Door Fan	Remote E-	STOP	нѕ	0.003 G	HSI	55406.000				
Ground Fault			HS RTD	16775000.	HS RTD I	354354.00				
Emergency Stop			Rack RTD	16713332.	Rack RTD I	0.000 A				
Smoke	WRITE HS DAG	C <b_hdice:< td=""><td>Rack RH</td><td>56545.000</td><td>Rack RH I</td><td>0.000 A</td></b_hdice:<>	Rack RH	56545.000	Rack RH I	0.000 A				
Transistor Fault	WRITE PT DAC	B_HDICE:S	Spare 1	646546.00	Spare 1	0.000 C				
			Spare 2	5656.000	Spare 2	0.000 C				




MOLLER – Mapping REQUIREMENTS

Mapping specification - definition wrt the accuracy and location requirements.

- Mapping design tool for mapping all sector plus the central bore.
- Uncertainty in variation of field from sector to sector (TDR)
- Modification(s) to OPERA model coil geometry to reproduce to measured field map

Complete Magnet – after assembly of magnet

- BMOD measurements (radially focusing component of field, BMOD) along Z in an open sector at r = 135 mm (TBR)
- Determination of magnetic center, measurement of any dipole moment in the bore
- Stray field measurements (location of 5 Gauss line)





Mapping Tool used in HALL B Torus/Solenoid


- Precisely machined upstream and downstream plates
- The plates will be surveyed prior to install to know hole locations
- Precise pins locate and orient the carbon fiber tubes
- Pins assure locating/repeatability of carbon fiber tubes to 0.05mm
- Linear slide/motor/controller accurate to 0.010mm

Mapping Tool Operation-Mapping the Bore

- The bore has a total of seven locations mapped in CLAS 12 Torus
- The center tube is offset from the collar center to take the 2.5cm radius measurement
- The assembly is rotated for each angle while maintaining the required local coordinate system orientation










Component	Safety Analysis	Additional steps
All Magnet Power supply	6210 Electrical Safety Manual Electrical Safe Work Practice	 NFPA 70E, 2015 - Standards for Electrical Safety in the Workplace National Electric Code (NEC) Handbook DOE-HDBK-1092, 2013 - Department of Energy Electrical Safety Handbook ES&H Manual 6230 Electrical Safety Manual JLAB-6220 AC Electrical Equipment Safe Work Program
Electrical and Instrumentation feedthroughs	6210 Electrical Safety Manual Electrical Safe Work Practice, Section 4. 6.	
Stored energy in the magnet	6210 Electrical Safety Manual Electrical Safe Work Practice, Section 4. 6.	
Hi-Pot test (leakage current test)	Hi-Pot test voltage 500V or 1.0kV/1.5kV (per ANSI/NETA ATA-2009), table 100.1 and apply temp comp factor based on table 100.14 or NFPA70 table 310.15(B)(2)(a)	Calculations



BACK UP





MPS Prototype – DS3 P6 Schedule

ID	Task Name		Start	Finish	Feb '22	Mar '22 A	or '22 M	av '22 Jun	22 Jul 22	Aug '22 S	en '22 Oct '22	Nov '22	Dec '22 Jan	'23 Feb '23 Ma	ar '23 Apr '23	May 23 Ju	un '23
1	Order Placement		14 Feb '22	14 Feb '22	*					They are to		1101 22		25 110 25 110		11107 25 130	
2	Technical Design Report (TDR)	09 Jun '22	09 Jun '22													
3	TDR Technical Design Rev	iew (Approval)	26 Aug '22	26 Aug '22													
4	Completion of Manufactu	ring	24 Feb '23	24 Feb '23													
5	FAT Factory Acceptance T	ests	31 Mar '23	31 Mar '23										T			
6	Delivery to JLAB		05 May '23	05 May '23													
7	SAT Site Acceptance Tests	;	02 Jun '23	02 Jun '23												No.	
8	DS Torus - 3 (4000 A 60 V	(240 kW))	09 Mar '22	30 Jun '23													
9	Design		09 Mar '22	09 Jun '22													
10	TDR approval		10 Jun '22	26 Aug '22				2									
11	Detailled drawings & Bo	oMs	27 Jun '22	23 Sep '22										E ^	- T		
12	Critical and LLT compor	nents procurement	09 May '22	24 Jan '23											NI —		
13	FPGAs		20 Jun '22	27 Jan '23					+					- Fac	tory		
14	PCBs		10 Jun '22	22 Dec '22				2						- 100	lory		
15	Ceramics capacitors		11 Jul '22	16 Dec '22										accer	otance		
16	Control boards		23 Dec '22	02 Feb '23									*		stariee		
17	IGBTs		15 Jun '22	29 Nov '22					+					te	est		
18	Diodes		11 Jul '22	16 Dec '22					*								
19	Procurement (SLT asser	mbly items)	11 Nov '22	02 Feb '23								*					
20	Production & Assembly	1	14 Nov '22	24 Feb '23													
21	Preparation & FAT		27 Feb '23	31 Mar '23										*			
22	Dismantling & Packing		03 Apr '23	07 Apr '23											* 5		
23	Transportation		10 Apr '23	05 May '23											<u> </u>		
24	Installation		08 May '23	19 May '23												* _	
25	Preparation & SAT		22 May '23	02 Jun '23								N/c	ow			*	
26	Delivery of complete de	ocumentation	30 Jun '23	30 Jun '23								INC	Jvv				
														iest	: plan 🚊		
		Task	_	Project	Summary	0	1	Inactive	Milestone	0	Manual S	ummary Rollu	p	Deadline	4	r	
Projec	ct: JLAB - DS Torus 3	Split		Externa	Tasks			Inactive	Summary	0	Manual S	ummary	0	Progress	-		•
Date:	23 Sep '22	Milestone	•	Externa	Milestone	•		Manual	Task		Start-only	r	E	Manual Pro	gress -		
		Summary	-	Inactive	Task			Duration	-only		Finish-on	y	а —				
														JLAB	- DS Torus 3 -	Main Project So	chedule



MPS – Schedule for other 4 (US, DS1, 2, and 4)

D	Task Name	Start	Finish	2 M	Half 2, 2 M J	022	Half 1, 2023	3 м	Half 2, 202	3	Hai	f 1, 2024	м Г м	Half 2, 202	4 c	N
1	DS Torus - 3 (4000 A 60 V (240 kW) (PROTOTYPE)	09 Mar '22	30 Jun '23		M J	2	N J	M			N		M			
2	Design	09 Mar '22	09 Jun '22		11 1											
3	TDR approval	10 Jun '22	26 Aug '22		*	-										
4	Detailled drawings & BoMs	27 Jun '22	23 Sep '22												1 1	
5	Critical and LLT components procurement	09 May '22	24 Jan '23													
6	FPGAs	20 Jun '22	27 Jan '23		+											-
7	PCBs	10 Jun '22	22 Dec '22		+	1			<u> </u>							-
8	Ceramics capacitors	11 Jul '22	16 Dec '22	<u> </u>					<u> </u>							
9	Control boards	23 Dec '22	02 Feb '23	<u> </u>					<u> </u>							-
10	IGBTs	15 Jun '22	29 Nov '22		+											-
11	Diodes	11 Jul '22	16 Dec '22	<u> </u>	+				<u> </u>		<u> </u>				<u> </u>	
12	Procurement (SLT assembly items)	11 Nov '22	02 Feb '23	<u> </u>		1			<u> </u>						+ +	
13	Production & Assembly	14 Nov '22	24 Feb '23	<u> </u>)	<u> </u>							
14	Preparation & FAT	27 Feb '23	31 Mar '23					-	<u>+</u>							
15	Dismantling & Packing		07 Apr '23				<u> </u>	_		•						· —
16		03 Apr '23						— I		2 NI		001	110		(م ما ـ	
	Transportation	10 Apr '23	05 May '23	<u> </u>				— J	uly 202	3-IN	OV 20	JZ4		IVION	thsi	
17	Installation	08 May '23	19 May '23				<u>├───</u> ──┤	_ -	- , = - =				, = -		/	
18	Preparation & SAT	22 May '23	02 Jun '23				<u>├───</u>				I	<u> </u>			+ +	
19	Delivery of complete documentation	30 Jun '23	30 Jun '23					_								-
20	Design (US Torus & DS Torus 1-2-4) - PURCHASE ORDER RECEI		14 Jul '23			_		_			h					
21	Dimensioning and Basic Simulations	03 Apr '23	14 Apr '23					-								
22	Dimensioning and Simulations specific for each model	17 Apr '23	12 May '23					*								
23	Electric design for the cabinets	01 May '23	26 May '23													
24	Custom components specifications and preparation of FDR	29 May '23	23 Jun '23													
25	Detailed Mechanical Design of the cabinets	29 May '23	23 Jun '23						*							
26	Codification of components, BOM , Production Specification	s 05 Jun '23	30 Jun '23													
27	Control Integration and functional validation	05 Jun '23	30 Jun '23						*							
28	TDR Approval	03 Jul '23	14 Jul '23						1 × 1							
29	Operations	17 Jul '23	12 Jul '24													
30	Procurement critical components	17 Jul '23	02 Feb '24						*		1	-			1 1	
31	Procurement LLT items	06 Nov '23	02 Feb '24								+					
32	Procurement SLT items	08 Jan '24	02 Feb '24						<u>+</u>							
33	Assembly	05 Feb '24	17 May '24	<u> </u>					<u> </u>							
34	US torus	05 Feb '24	29 Mar '24	<u> </u>					<u> </u>			-			<u> </u>	
35	DS Torus - 1	26 Feb '24	19 Apr '24	<u> </u>					<u> </u>		<u> </u>					
36	DS Torus - 2	11 Mar '24	03 May '24	<u> </u>		_			<u> </u>					<u> </u>		
37	DS Torus - 4	25 Mar '24	17 May '24	<u> </u>				_					- í -	<u> </u>		
38	FAT Preparation (10 days per unit)		12 Jul '24						<u> </u>					h		
39		20 May '24		<u> </u>		_		_							<u> </u>	
	FAT	15 Jul '24	30 Aug '24					_							7	
40	US torus	15 Jul '24	02 Aug '24		<u> </u>	_	┼───┤		+							
41	DS Torus - 1	22 Jul '24	09 Aug '24													
42	DS Torus - 2	29 Jul '24	16 Aug '24			_		_	ļ							4
43	DS Torus - 4	05 Aug '24	23 Aug '24													⊥∟
44	Dismantling & Packing	26 Aug '24	30 Aug '24			_								7		4
45	FAT report (5 days per unit)	02 Sep '24	27 Sep '24													
	final documentation, operating manuals	30 Sep '24	18 Oct '24												*	
46	The second station	02 Sep '24	27 Sep '24												*	
46 47	Transportation	30 Sep '24	18 Oct '24													
46 47 48	On-site commissioning and Tests														* _	
46 47		30 Sep '24	11 Oct '24												*	
46 47 48	On-site commissioning and Tests		11 Oct '24 18 Oct '24													
46 47 48 49	On-site commissioning and Tests Installation	30 Sep '24														3
46 47 48 49 50	On-site commissioning and Tests Installation SAT Delivery of complete documentation	30 Sep '24 14 Oct '24 15 Nov '24	18 Oct '24													9
46 47 48 49 50	On-site commissioning and Tests Installation SAT Delivery of complete documentation Task	30 Sep '24 14 Oct '24 15 Nov '24 Project Summary	18 Oct '24	I Inactiv	re Milestone	,	Manual Summary Ro	ollup	Deadline		÷					9
46 47 48 49 50 51 Projec	On-site commissioning and Tests Installation SAT Delivery of complete documentation Task t: 21-R405082 Split	30 Sep '24 14 Oct '24 15 Nov '24 Project Summary	18 Oct '24		e Milestone e Summary I	,	Manual Summary Ro 1 Manual Summary	ollup	Deadline Progress		÷					9
46 47 48 49 50 51 Projec	On-site commissioning and Tests Installation SAT Delivery of complete documentation Task	30 Sep '24 14 Oct '24 15 Nov '24 Project Summary	18 Oct '24		e Summary I	,		ollup C		rogress	¢					<u>æ</u>
46 47 48 49 50 51 Projec	On-site commissioning and Tests Installation SAT Delivery of complete documentation Task t: 21-0405082 Split	30 Sep '24 14 Oct '24 15 Nov '24 Project Summary External Tasks	18 Oct '24 15 Nov '24	Inactiv Manua	e Summary I	,	1 Manual Summary	ollup C	Progress	rogress	÷	_				<u>8</u>

- Schedule Projected for other 4 (US, DS1, 2, and 4) from vendor.
- All critical items viz FPGA, DCCT will be on hand with OCEM
- The schedule will be evaluated after the prototype DS3 MPS installed and commissioned in the test lab.



Electrical connect between MPS and Magnet

